


| Description | Commercial | Residential |  | Style |
|-----------------|---|--|---|--|
| | Vertical Picket | 3/4" Pre-Galvanized Square Steel Tube 18 Gauge Thickness | | 5/8" Pre-Galvanized Square Steel Tube 18 Gauge Thickness |
| Horizontal Rail | 1-1/4" Pre-Galvanized Square Steel Tube 14 Gauge Thickness | 1-1/4" Pre-Galvanized Square Steel Tube 14 Gauge Thickness | | |
| Post | 2-1/2" Pre-Galvanized Square Steel Tube 14 Gauge | 2" Pre-Galvanized Square Steel Tube 14 Gauge | | |
| Post Cap | Die Cast Zinc or Polymer Materials Available | Die Cast Zinc or Polymer Materials Available | | |
| Finial | Die Cast Zinc or Polymer Materials Available | Pressed Point | | |
| | Size Specifications: Installed Height 4, 5, 6, and 8 foot Heights Panel Length 93-1/8 Inches Picket Spacing 6" or 4.5" on Center | Size Specifications: Installed Height 4, 5, and 6 foot Heights Panel Length 93-1/8 Inches Picket Spacing 6" or 4" on Center | Mailing Address: P.O. Box 22704 Jackson, MS 39225 | |